



Trujillo Construction

Project:
141 N Anita
Los Angeles, CA 90049

Date: 9/18/26

Project Overview

Phase 1 requires a complete demolition of the following: existing residence, detached garage, foundations/slabs, hardscape, south side landscape clearance, and the non-retaining CMU wall currently separating 141 and 135 N Anita. 135 N Anita is to remain protected.

Scope of Work

Pre-construction / Permitting:

Survey coordination, demolition/site plan, environmental testing coordination, LADBS demolition permitting/clearances, required notifications and consultant coordination.

Utility Disconnects:

Coordinate electric and gas service abandonment/removal; water disposition; sewer locate/cap; telecom/private utility disconnects and utility locating.

Site Protection:

Utilize current temporary fencing, dust/erosion controls and protection of 135 N Anita, sidewalk, curb, street and adjacent improvements.

Complete Demolition:

Remove existing residence, detached garage, slabs, conventional foundations/footings, driveway, patios, walks, landscape/irrigation, miscellaneous site improvements and non-retaining CMU common wall.

Hauling / Site Clearing:

Load, haul, recycle and legally dispose of demolition debris and green waste; maintain disposal documentation.

Backfill / Rough Grade:

Backfill demolition excavations and rough-grade the cleared site for safe temporary drainage and Phase 2 handoff.

Cost Breakdown

Phases	Cost
Permits	\$4,000
Environmental Testing	\$2,700
Demolition	\$85,000
- Utility Disconnections	
- Main House	
- Detached Garage	
- CMU Wall in-between 135 N Anita & 141 N Anita	
- Landscape Removal lining south side CMU Wall	
Soil Grading & Removal	\$45,000
Extra Soil Hauling Allowance	\$1,500 per load
Total	\$136,700 *extra soil hauling not included
Option 2: General Contractor Overhead & Management	\$16,500
Option 2 Total	\$153,200

Anticipated Timeline

Preconstruction / testing / permits:

Approx. 4-8+ weeks, subject to agency review, utility scheduling, environmental findings and required notices.

Physical demolition / clearing:

Approx. 2-4 weeks after all permits, clearances and utility releases are complete.

Estimated Phase 1 duration:

Approx. 6-12+ weeks from authorization; schedule will be updated once agency/utility dates and environmental results are known.

Allowances / Exclusions / Assumptions

Pricing is based on the defined Phase 1 scope, including established permit and environmental testing costs, and assumes conventional demolition conditions, foundations/footings, and a non-retaining CMU wall. Hazardous-material abatement, contaminated soil, concealed utilities, unusual foundations, or other unforeseen conditions are excluded and subject to change order. Final site condition includes backfill and rough grading for safe drainage and Phase 2 handoff.

Agreement Signatures

Contractor:

Date:

Owner Acceptance:

Date: